YOUR BUSINESS NAME

ESTIMATE

Address: _____

Phone: _____

Email: _____

License #: _____

Estimate #: _____

Date: _____

Valid until: _____

PREPARED FOR

JOB ADDRESS

Job: Basement mold remediation, 80 sq ft affected

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Containment setup Poly barriers, zipper door, negative air	1	job	$650.00	$650.00
HEPA air scrubber Per unit per day	4	unit-day	$95.00	$380.00
Remove affected drywall Bag and seal for disposal	80	sq ft	$6.00	$480.00
HEPA vacuum and clean framing Wire brush, HEPA vacuum, damp wipe	80	sq ft	$4.50	$360.00
Antimicrobial and encapsulant Applied to cleaned framing	80	sq ft	$1.75	$140.00
PPE and disposal Respirators, suits, sealed disposal	1	job	$225.00	$225.00

Example prices are illustrative. Replace them with your own.

Subtotal	$2,235.00
Sales tax	
TOTAL	
Deposit due on approval (30%)	$670.50

TERMS

- The moisture source must be fixed for remediation to last; repairs to the source are not included unless listed.
- Post-remediation verification, if required, is performed by an independent assessor.
- This estimate is valid for 30 days from the date above.
- Work not listed above is not included and will be quoted separately.

Customer approval

Signature: _____ Date: _____