YOUR BUSINESS NAME

ESTIMATE

Address: _____

Phone: _____

Email: _____

License #: _____

Estimate #: _____

Date: _____

Valid until: _____

PREPARED FOR

_____

_____

_____

JOB ADDRESS

_____

_____

_____

Job: Architectural shingle re-roof, 28 squares

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Tear-off Remove one layer of shingles and underlayment	28	sq	$75.00	$2,100.00
Architectural shingles Installed, including starter and hip/ridge cap	28	sq	$365.00	$10,220.00
Synthetic underlayment and ice barrier Full deck coverage, ice barrier at eaves and valleys	28	sq	$45.00	$1,260.00
Drip edge and flashing New drip edge, step and counter flashing	1	job	$850.00	$850.00
Decking replacement (if needed) 7/16 OSB, per sheet as found	6	sheet	$85.00	$510.00
Ridge vent Shingle-over ridge vent	40	lf	$9.00	$360.00
Dumpster and cleanup Disposal, magnetic nail sweep	1	job	$650.00	$650.00

Example prices are illustrative. Replace them with your own.

Subtotal	$15,950.00
Sales tax	_____
TOTAL	_____
Deposit due on approval (33%)	$5,263.50

TERMS

- Decking replacement is billed per sheet at the rate shown, only for sheets found damaged after tear-off.
- Work is weather dependent; start dates may move for rain or high wind.
- This estimate is valid for 30 days from the date above.
- Work not listed above is not included and will be quoted separately.

Customer approval

Signature: _____ Date: _____